ENGINEERING DEPARTMENT.

WATER-SUPPLY DIVISION.

Abstract Notification.

The attention of the public is invited to the notice dated 8th March 1918; calling for tenders for the supply of crude oil or liquid fuel for the use of Water-Supply Division, until the 1st May 1918, published on page 247, Part IV of the *Mysore Gazette.*

S. SRINIVASA AIYAR,
Executive Engineer.

KOLAR DIVISION.

Dated 22nd March 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer Kolar Division, up to 15th April 1918, for restoring Vaichakurhalli tank, Registered No. 444 of Chintamani Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1918.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Kolar, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring Vaichakurhalli tank, Registered No. 444 of Chintamani Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned

Approximate estimate of quantities for restoring Vaichakurhalli tank, Registered No. 444 of Chintamani Taluk.

Items of work	Per	Quantity
1. Earthwork with consolidation	C. yd.	13,735
2. Turfing	S. yd.	14,586
3. Fixing new grade stones with bed and index stones including chiselling figures and painting.	Each	40
4. Tank Register No. stone	"	1
5. Date stone	"	1
6. Gauge stone	"	1
Waste weir 200' long at R. L. 50·00.		
1. Concrete in surki mortar	C. ft.	770
2. Burnt brick in surki mortar	"	3,812
3. Burnt stone slabs dressed	S. ft.,	564
4. Plastering with surki mortar	Sqr.	14·14
5. Rough stone work new	C. yd.	688
6. Providing jaggles	No.	15
Ane across kody halla 70' long at R. L. 48·00.		
1. Burnt brick in surki mortar	C. ft.	1,303
2. Plastering with surki mortar	Sqr.	5·50
3. Burnt stone slabs dressed	Sq. ft.	140
4. Rough stone work new	C. yd.	148
Constructing a Regulator for channel at R. L. 46·50 of 1 vent 3'×3½'.		
1. Burnt brick in surki mortar	C. ft.	86
2. Burnt stone slabs dressed	S. ft.	35
3. Rough stone work new	C. yd.	7
4. Teakwood shutters with iron works road, etc., complete and cutting grooves to fix shutters (3½'×3½') of 2" thick.	Each	1
5. Plastering with surki mortar	Sqr.	60